

ADDENDUM 1

ARTICLE 3 – BID SCHEDULE (REBID)

PROJECT NO. 26-PW-002

3.0 BID SCHEDULE

CONTRACT FOR: CITY CENTRE IMPROVEMENT DISTRICT IMPROVEMENTS (REBID)
Project No. 26-PW-002

The undersigned bidder, having examined and determined the scope of the Contract Documents, hereby proposes to perform the work described therein for the following unit prices or lump sum amounts.

- Notes: 1. Bids shall include sales tax and all other applicable taxes and fees. All bids shall be checked for errors. If errors are made, unit prices shall govern and corrections will be made according to the unit price and totals will be revised to reflect the corrections.
2. Upon request Bidder may be provided with an active Excel spreadsheet for the insertion of bid amounts.

Bid Item #	Spec No.	Item Description	Qty.	UNIT	UNIT AMOUNT	TOTAL
		Main Street				
1	12.1	Project Mobilization	1	LS		\$ -
2	12.2	Project Traffic Control	1	LS		\$ -
3	12.5	3 Inches AC Pavement	15,789	SY		\$ -
4	12.6	10 Inches Aggregate Base Course	15,789	SY		\$ -
5	12.4	Subgrade Preparation	15,789	SY		\$ -
6	12.5	Fog Seal	15,789	SY		\$ -
7	12.8	6 Inch Vertical Curb & Gutter MAG 220-A	8,403	LF		\$ -
8	12.8	6 Inch Wedge Curb (Traffic Island)	473	LF		\$ -
9	12.7	Concrete Sidewalk	45,223	SF		\$ -
10	12.9	ADA Ramp MAG 236-5 Single	9	EA		\$ -
11	12.9	ADA Ramp MAG 238-1 Single	9	EA		\$ -
12	12.7	Concrete Aprons	3,802	SF		\$ -
13	12.7	Concrete Valley Gutter	2,192	SF		\$ -
14	12.20	8 Inch PVC SDR 35 Sewer Line	2,280	LF		\$ -
15	12.20	48 Inch Diameter Sewer Manhole	13	EA		\$ -
16	12.21	10 Inch PVC C900 Water Line	2,317	LF		\$ -
17	12.21	10 Inch Ductile Iron Pipe	669	LF		\$ -
18	12.21	10 Inch Gate Valves w/ Box & Cover	7	EA		\$ -
19	12.21	Fire Hydrant Assembly	5	EA		\$ -

ADDENDUM 1

20	12.21	8 Inch PVC C900 Water Line	462	LF		\$ -
21	12.21	8 Inch Gate Valves w/ Box & Cover	14	EA		\$ -
22	12.5	Pavement Replacement (Marina Utility Crossing)	797	SY		\$ -
23	12.21	2 Inch Air Release Valves	2	EA		\$ -
24	12.21	2 Inch Potable Curb Stop	10	EA		\$ -
25	12.26	Barracade MAG STD DET 130 Type A	2	EA		\$ -
26	12.28	Survey Monuments MAG STD DET 120-1 Type B	15	EA		\$ -
27	12.25	Utility Crossings	8	EA		\$ -
28	12.22	Street Lights	21	EA		\$ -
29	12.13 12.14	Striping and Signage	1	LS		\$ -
SUBTOTAL (Main Street)						\$ -
Riverview Drive						
30	12.5	3 Inches AC Pavement	892	SY		\$ -
31	12.6	10 Inches Aggregate Base Course	892	SY		\$ -
32	12.4	Subgrade Preparation	892	SY		\$ -
33	12.5	Fog Seal	892	SY		\$ -
34	12.8	6 Inch Vertical Curb & Gutter MAG 220-A	374	LF		\$ -
35	12.7	Concrete Sidewalk	1,882	SF		\$ -
36	12.22	Street Lights	1	EA		\$ -
37	12.13 12.14	Striping and Signage	1	LS		\$ -
SUBTOTAL (Riverview Dr)						\$ -
Oatman Road						
38	12.5	3 Inches AC Pavement	4,625	SY		\$ -
39	12.6	10 Inches Aggregate Base Course	4,625	SY		\$ -
40	12.4	Subgrade Preparation	4,625	SY		\$ -
41	12.5	Fog Seal	4,625	SY		\$ -
42	12.8	6 Inch Vertical Curb & Gutter MAG 220-A	1,724	LF		\$ -
43	12.7	Concrete Sidewalk	6,807	SF		\$ -
44	12.9	ADA Ramp MAG 236-1 Single	2	EA		\$ -
45	12.21	10 Inch PVC C900 Water Line	772	LF		\$ -

ADDENDUM 1

46	12.21	10 Inch Ductile Iron Pipe	166	LF		\$ -
47	12.21	10 Inch Gate Valves w/ Box & Cover	3	EA		\$ -
48	12.21	8 Inch PVC C900 Water Line	110	LF		\$ -
49	12.21	8 Inch Gate Valves w/ Box & Cover	2	LF		\$ -
50	12.21	2 Inch Air Release Valves	1	EA		\$ -
50A	12.21	2 Inch Potable Curb Stop	3	EA		\$ -
51	12.21	Fire Hydrant Assembly	1	EA		\$ -
52	12.20	8 Inch PVC SDR 35 Sewer Line	730	LF		\$ -
53	12.20	48 Inch Diameter Sewer Manhole	2	EA		\$ -
54	12.22	Street Lights	4	EA		\$ -
55	12.13 12.14	Striping and Signage	1	LS		\$ -
SUBTOTAL (Oatman Rd)						\$ -
SR 95 Improvements						
56	12.5	3 Inches AC Pavement	192	SY		\$ -
57	12.6	10 Inches Aggregate Base Course	192	SY		\$ -
58	12.4	Subgrade Preparation	192	SY		\$ -
59	12.5	Fog Seal	192	SY		\$ -
60	12.26	Barracade MAG STD DET 130 Type A	1	EA		\$ -
61	12.8	7 Inch Vertical Curb & Gutter ADOT C-05.10	156	LF		\$ -
62	12.7	Concrete Sidewalk	1,078	SF		\$ -
63	12.9	ADA Ramp MAG 236-5 Single	2	EA		\$ -
64	12.7	Concrete Valley Gutter	405	SF		\$ -
65	12.27	Porkchop	1	EA		\$ -
SUBTOTAL (SR 95 Improvements)						\$ -
Drainage and Misc Improvements						
66	12.15	60 Inch HDPE Storm Drain Pipe	3,549	LF		\$ -
67	12.19	Concrete Head Wall ADOT Standard Detail SD 6.30	6	EA		\$ -
68	12.15	36 Inch HDPE Storm Drain Pipe	1,016	LF		\$ -
69	12.15	24 Inch Storm Drain Pipe	21	LF		\$ -
70	12.15	18 Inch Storm Drain Pipe	384	LF		\$ -
71	12.19	Head Wall MAG STD 501-1"U" Type	6	EA		\$ -

ADDENDUM 1

72	12.19	Head Wall MAG STD 501-2 "U" Type	6	EA		\$ -
73	12.19	Head Wall MAG STD 501-1 "L" Type	1	EA		\$ -
74	12.17	Catch Basins MAG 533 SGL 10' WING	1	EA		\$ -
75	12.17	Catch Basins MAG 533 SGL 6' WING	3	EA		\$ -
76	12.17	Catch Basins MAG 533 DBL 3' WING	5	EA		\$ -
77	12.16	Storm Drain Manholes	1	EA		\$ -
78	12.3	Small Channels & Roadway Excavation	39,000	CY		\$ -
79	12.24	Channel Shot-Crete (East of Main Street)	1,378	SY		\$ -
80	12.24	Channel Shot-Crete (West of Main Street)	7,017	SY		\$ -
81	12.23	Channel Rip Rap D50 = 12 Inch	170	CY		\$ -
82	12.23	Channel Rip Rap D50 = 8 Inch	2,624	CY		\$ -
83	12.23	Channel Rip Rap D50 = 6 Inch	3,777	CY		\$ -
84	12.23	Channel Rip Rap D50 = 12 Inch Grouted	671	CY		\$ -
85	12.3	Retention Basin and Main Channel Grading	128,676	CY		\$ -
86	12.29	Wrought Iron Fencing	3,932	LF		\$ -
87		SWPPP	1	LS		\$ -
88	12.25	2 Inch Irrigation Sleeves	8	EA		\$ -
SUBTOTAL (Drainage & Misc Imp)						\$ -
Parkside Lane						
89	12.5	3 Inches AC Pavement	11,072	SY		\$ -
90	12.6	10 Inches Aggregate Base Course	11,072	SY		\$ -
91	12.4	Subgrade Preparation	11,072	SY		\$ -
92	12.5	Fog Seal	11,072	SY		\$ -
93	12.8	6 Inch Vertical Curb & Gutter MAG 220-A	6,725	LF		\$ -
94	12.7	Concrete Sidewalk	40,142	SF		\$ -
95	12.9	ADA Ramp MAG 236-5 Single	6	EA		\$ -
96	12.7	Concrete Aprons	1,125	SF		\$ -
97	12.7	Concrete Valley Gutter	348	SF		\$ -
98	12.21	8 Inch PVC C900 Water Line	2,855	LF		\$ -
99	12.21	8 Inch Ductile Iron Pipe	778	LF		\$ -
100	12.21	8 Inch Gate Valves w/ Box & Cover	8	EA		\$ -

ADDENDUM 1

101	12.21	2 Inch Air Release Valves	4	EA		\$ -
102	12.21	2 Inch Potable Curb Stop	4	EA		\$ -
103	12.21	Fire Hydrant Assembly	1	EA		\$ -
104	12.20	8 Inch PVC SDR 35 Sewer Line	2,075	LF		\$ -
105	12.20	48 Inch Diameter Sewer Manhole	8	EA		\$ -
106	12.28	Survey Monuments MAG STD DET 120-1 Type B	7	EA		\$ -
107	12.22	Street Lights	18	EA		\$ -
108	12.13 12.14	Striping and Signage	1	LS		\$ -
SUBTOTAL Parkside Lane						\$ -
109	9.33	OWNER'S CONTINGENCY	1	LS	\$900,000.00	
Grand Total						\$ -

Total Bid Amount (Items 1 through 109 above): _____ (In Words). (\$_____.00) Calendar Days Vendor requires to Complete Total Project: **150** Calendar days or less after Notice to Proceed. This Proposal is submitted by _____, a corporation or limited liability company organized under the laws of the State of _____, or a partnership consisting of _____ or individual trading as _____ and is the holder of Arizona Contractor's License No.\ _____: Bullhead City License No:\ _____ (City License not required at time of Bid but must be obtained prior to issuance of Notice to Proceed.)

Respectfully submitted,

Company Name

Signature of Authorized Person

Address

Printed Name

City State Zip

Title

Telephone

Telephone

Email

Email

Fax

Fax